SECTION 151

SOLID WASTE CONSTRUCTION

- **151-1 GENERAL -** Solid Waste enclosures shall be constructed in accordance with the requirements of these Construction Standards and as recommended by the manufacturer. These Construction Standards and manufacturer's guidelines shall be present at the construction site at all times.
- **151-2 APPROVED PLANS -** Planning Department and Building Division approvals of the solid waste enclosure shall be obtained prior to beginning construction.
- **151-3 INSPECTION -** Enclosures shall be inspected per the following procedure:
 - 1. Contractor shall meet with the designated Development Services Construction Inspector prior to beginning work.
 - **2.** A City approved detailed structural design for the enclosure shall be provided to the inspector.
 - **3.** Footings, enclosure floor reinforcements, approach floor reinforcement, vertical wall reinforcement, and bollards shall be inspected prior to pouring concrete.
 - **4.** Gates shall be inspected prior to and after installation.
 - **5.** Signage and striping shall be inspected prior to and after installation.
- **151-4 PUNCHLIST PROCESS** When all improvements are substantially complete, the contractor shall provide a written request for a punchlist inspection of the improvements.
- **151-5 MATERIALS** Materials shall be as specified on these Construction Standards and as approved by the architect and the City for the specific project.